BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54620

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Improvements to Roads and Drains at Chikkavenkatappa Layout, Deshbandunagara and Surrounding area in Ward No.13, (Doddabommasandra)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Subbareddy K V ( )	
				In Figures	In Words
1	49.50	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge	Cum	1364.12	Rupees One Thousand Three Hundred Sixty Four and Twelve Paise Only
2	290.00	Providing, laying and spreading available soil in the embankment on a prepared surface, pulverising, mixing the spreaded soil in place with Soil stabilisor with 2% of slaked lime using Binder spreader Machine having minimum content of 70% of CaO, grading with the motor grader and compacting with the road roller at OMC to the desired density to form a layer of improved embankment. (By Mechanical Means	Cum	722.75	Rupees Seven Hundred Twenty Two and Seventy Five Paise Only
3	421.25	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	199.16	Rupees One Hundred Ninety Nine and Sixteen Paise Only
4	48.00	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	5946.89	Rupees Five Thousand Nine Hundred Forty Six and Eighty Nine Paise Only
5	105.60	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	6709.69	Rupees Six Thousand Seven Hundred Nine and Sixty Nine Paise Only
6	6.34	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	98690.11	Rupees Ninety Eight Thousand Six Hundred Ninety and Eleven Paise Only
7	286.20	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete.	Sqm	2016.88	Rupees Two Thousand Sixteen and Eighty Eight Paise Only
8	105.30	Construction of Dry Lean Cement Concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm,aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing	Cum	4309.73	Rupees Four Thousand Three Hundred Nine and Seventy Three Paise Only
9	105.30	Providing and constructing un-reinforced plain Cement Concrete Pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, primer, sealant, curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete MORTH Specification No.1501 . as per the directions of the Engineer-in-charge of the work.	Cum	6972.66	Rupees Six Thousand Nine Hundred Seventy Two and Sixty Six Paise Only

M.V. Subba Reddy

Executive Engineer,
Rajarajeshwarinagara Division,
BBMP, Bangalore.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Subbareddy K V ( )	
				In Figures	In Words
10	383.34	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3)	Cum	79.23	Rupees Seventy Nine and Twenty Three Paise Only
11	490.67	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	T.Km	112.43	Rupees One Hundred Twelve and Forty Three Paise Only
12	1.00	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1)Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a)Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2)A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test	Each	5004.25	Rupees Five Thousand Four and Twenty Five Paise Only
13	50.00	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete 0 to 50 m	Rmtr	282.29	Rupees Two Hundred Eighty Two and Twenty Nine Paise Only
14	50.00	50 to 100 m	Rmtr	354.32	Rupees Three Hundred Fifty Four and Thirty Two Paise Only
15	50.00	100 to 150 m	Rmtr	376.71	Rupees Three Hundred Seventy Six and Seventy One Paise Only
16	50.00	150 to 200 m	Rmtr	437.00	Rupees Four Hundred Thirty Seven Only
17	50.00	200 to 250 m	Rmtr	512.98	Rupees Five Hundred Twelve and Ninety Eight Paise Only
18	50.00	250 to 300 m	Rmtr	543.16	Rupees Five Hundred Forty Three and Sixteen Paise Only
19	50.00	300 to 350 m	Rmtr	603.51	Rupees Six Hundred Three and Fifty One Paise Only
20	60.00	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar - Medium duty	Rmtr	1881.58	Rupees One Thousand Eight Hundred Eighty One and Fifty Eight Paise Only
21	18.00	Providing 250mm dia PVC Pipe 6kg/cm	Rmtr	1070.74	Rupees One Thousand Seventy and Seventy Four Paise Only
22	1.00	Providing and fixing Borewell Cap & Clamp Set	Set	1752.12	Rupees One Thousand Seven Hundred Fifty Two and Twelve Paise Only

R.V. Subba Reddy

Executive Engineer,
Bytarayanapura Division,
BBMP, Bangalore.

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of Subbareddy K V ( )	
				In Figures	In Words
23	1.00	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, as per necessary ammendments and instructions of engineer incharge of work 12.50 HP - 90 LPM @ 264 m = 24 STG Outlet Dia - 2.00	No	61808.95	Rupees Sixty One Thousand Eight Hundred Eight and Ninety Five Paise Only
24	280.00	Providing, Laying and Fixing GI pipes conforming to IS 1239:1990 with latest amendments complete with GI fittings (excluding the cost of fittings) with cuts and threads wherever necessary, including testing for water tightness, with all lead and commissioning. (contractor will make his own arrangements for procuring water for testing) Medium Duty GI pipe of 50mm dia	M	466.26	Rupees Four Hundred Sixty Six and Twenty Six Paise Only
25	47.00	Providing wrought mild steel (galvanized) 50 mm dia GI collar confirming to IS 1239-II, 1991 with latest amendments if any.	No	213.17	Rupees Two Hundred Thirteen and Seventeen Paise Only
26	1.00	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments 50 mm	No	1241.00	Rupees One Thousand Two Hundred Forty One Only
27	1.00	Supply and delivery at site brand new best make starter/ control panel suitable for following HP centrifugal pump confirming with ISI mark and its latest amendments 10 to 120 HP centrifugal pump	No	34536.23	Rupees Thirty Four Thousand Five Hundred Thirty Six and Twenty Three Paise Only
28	580.00	Submersible Cable 1x3x6.0 Sq.mm	M	140.17	Rupees One Hundred Forty and Seventeen Paise Only
29	47.00	Labour charges for Erection of new / repaired submersible pump set along with GI pipes (32mm / 50mm), cable (New submersible pump set if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (Each length = 6 m)	Job	146.98	Rupees One Hundred Forty Six and Ninety Eight Paise Only
30	1.00	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws.	Each	284.23	Rupees Two Hundred Eighty Four and Twenty Three Paise Only
31	35.00	Providing, Supplying and fixing suitable for 1.1 KV class UG cable filled with necessary bitumen / insulating compound complete with terminals, clamps, bolts, nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work	Mtr	501.30	Rupees Five Hundred One and Thirty Paise Only
32	30.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. For Cutting Road Surface	Mtr	73.98	Rupees Seventy Three and Ninety Eight Paise Only
33	4.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV. 40mm dia GI pipe	Mtr	326.09	Rupees Three Hundred Twenty Six and Nine Paise Only
34	1.00	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc. 16Sqmm	No	262.82	Rupees Two Hundred Sixty Two and Eighty Two Paise Only
35	1.00	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia	Job	3650.25	Rupees Three Thousand Six Hundred Fifty and Twenty Five Paise Only
36	6.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. 32 Amps	No	169.37	Rupees One Hundred Sixty Nine and Thirty Seven Paise Only
37	1.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6-32Amps TPN	No	1669.38	Rupees One Thousand Six Hundred Sixty Nine and Thirty Eight Paise Only
38	23400.00	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete. 16SWG	Sq.Cm	0.34	and Thirty Four Paise Only

Executive Engineer,
Bytarayanapura Division,
BBMP, Bangalore.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Subbareddy K V ( )	
				In Figures	In Words
39	24.30	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm whevere necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	Cum	207.72	Rupees Two Hundred Seven and Seventy Two Paise Only
40	6.75	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately	Cum	451.85	Rupees Four Hundred Fifty One and Eighty Five Paise Only
41	150.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete., 75mm(weight of pipe -0.917 kg. 75 mm dia 6 KSC PVC pipe	Rmtr	204.41	Rupees Two Hundred Four and Forty One Paise Only
42	24.30	Refilling available earth around trenches / pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	100.26	Rupees One Hundred and Twenty Six Paise Only
43	5.00	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendment Size 65 mm	Each	1508.77	Rupees One Thousand Five Hundred Eight and Seventy Seven Paise Only

Signature of the Contractor

Executive Engineer,
Bytarayanapura Division
BBMP, Bangalore.

Executive Engineer,
Bytarayanapura Division,
BBMP, Bangalore.